



All tests reported herein have been performed in accordance with the laboratory's scope of accreditation

PO Box 285, Kumeu, Auckland, New Zealand. Phone: +64 9-415 2800 Mob +64 21-977 876.

TEST REPORT No. 14/06B

Page 1 of 5 pages

REFERENCE: Symonite Panels Ltd

PO Box 101-760 North Shore Auckland 0745

Performance tests on Symonite composite Aluminium cladding system in accordance New Zealand Building Code E2/VM1:

DATE OF TEST: 18 - 19 July 2014

SUMMARY

Series 1 Static pressure Water Penetration Test:

No water penetration observed.

Series 1 Cyclic pressure Water Penetration Test:

No water penetration observed.

Series 2 Static pressure Water Management Test:

No water penetration observed.

Series 2 Cyclic pressure Water Management Test:

No water penetration observed. Water not bridging onto plane of building wrap membrane

Series 3 Wet wall Test: Initial

Water penetration around window head flashing, crossing cavity onto plane of building wrap. No other water transfer to plane of building wrap

Series 3 Wet wall Test: Retest

Following the repair to the damaged head flashing, no further water penetration occurred associated with the window head flashing.

The test on the Symonite Panel cladding demonstrated that the following elements incorporated into the test sample complied with the E2/VM1requirements:

Vertical and horizontal panel joints

Internal corner detail

External corner detail

Alternative Window installations

Sill detail

Vented/ drained horizontal joint

DESCRIPTION:

The test sample consisted of a single storey timber framed structure, with stepped external face providing sample details of internal and external corners, two alternative window penetrations, a horizontal vented joint and a vented bottom plate. General details of the test structure as well as the details of the fixing methods and the panel joints are shown in the attached Symonite drawings. Sheets A - M.

Tested by:.....


The Symonite composite aluminium cladding system consists of a nominal 4mm thick panel with precoated aluminium faces and a composite polymeric core, which is fabricated using V

groove machining and folding into individual panels. The panels are fitted together with overlapping horizontal and vertical joints, incorporating aluminium extrusions riveted to the inner edge of the panel edges and fixed onto the support framing. With the exception of horizontal drained joints, all horizontal and vertical panel joints are subsequently filled with silicone sealants on PEF backing rod.

As the test sample had been previously tested using AS/NZS 4284: 2008 procedures to higher ULS test pressures than the notional ± 2500 Pa ULS for



E2/VM1 the previously installed transparent rigid air barrier of 4.5 mm clear



However to comply with the principle of E2/VM1 which uses a full internal lining together with a possibly permeable building wrap, 100 mm diameter openings were cut through the 4.5 mm polycarbonate sheet at every frame opening except for those designated as viewing points for the Series 1 & 2 water penetration tests. The remainder of the internal face was lined with plywood, leaving the original section of polycarbonate at each internal view point opening.

TEST METHOD

Testing of the Symonite Panels cladding system installation was conducted using the NZ Building Code E2/VM1 test procedure.

The VM1 test method is a specific subset of the AS/NZS 4284: 2008 Water penetration Test with additional procedures evaluating possible leakage through external cladding defects. (Water Management tests)

The initial Series 1 test is specified as a 15 minute exposure to a static pressure of 455 Pa, followed by two sequential periods of 5 minutes at cyclic pressures of 227 - 455 Pa and 455–910 Pa respectively. The Series 2 Water Management test consists of a repeat of the static and cyclic Series 1 pressure sequence following the drilling of several 6 mm holes through the cladding face simulating possible defects in the external seals or cladding.

The following photos show the locations of the specified 6 mm diameter holes drilled for the Water Management test.

Tested by:

Checked by...











Following the removal of all internal linings, the test specimen was subjected to the Wet wall test, being the application of the water spray at a static pressure of 50 Pa across the cladding face.

As the results below indicate, water penetration onto the plane of the building wrap was visible during the Series 3: Wet Wall Test Static Water penetration test. The clients subsequently removed the adjacent external panel and located a hole in the back corner of the head flashing that was allowing water to flow into the rear of the cavity, onto the plane of the building wrap. It was apparent that the head flashing damage had



Hole in rear of head flashing

Tested by:

Checked by.....

occurred following repairs to the window sill installation after water penetration occurred during the AS/NZS 4284 preliminary tests.

RESULTS

ESULTS	
Series 1: Static Water penetration Test pressure 455 Pa Duration 15 mins	No water penetration visible on interior of cladding and around penetrations
Series 1: Cyclic Water penetration Test pressure 227 - 454 Pa Duration 5 mins Test Pressure 455 – 910 Pa	No water penetration visible on interior of cladding and around penetrations No water penetration visible on interior of cladding and
Duration 5 mins Series 2: Water Management	No water penetration visible on interior of cladding and
Tests Static Water penetration Test pressure 455 Pa Duration 15 mins	around penetrations
Series 2: Water Management Tests Cyclic Water penetration Test pressure 227 - 455 Pa Duration 5 mins Test Pressure 455 – 910 Pa	No water penetration visible on interior of cladding and around penetrations No water penetration visible on interior of cladding and around penetrations. Water not bridging onto plane of
Duration 5 mins Series 3: Wet Wall Test Static Water penetration	building wrap membrane. Water penetration
Test pressure 50 Pa Duration 15 mins	around window head flashing, crossing cavity onto plane of building wrap. No other water transfer to plane of building wrap
	West of the second seco

Retest following repair to window head flashing

Tested by:

Checked by.....

Series 3: Wet Wall Test Static Water penetration Test pressure 50 Pa Duration 15 mins No water penetration around window head flashing, water transfer to plane of building wrap
--

Authorised Signatory 30 July 2014

Tested by:....